

Bid Addendum Report

Fikkal Rural Municipality, Sindhuli

Fikkal Rural Municipality, Sindhuli
Fikkal, Sindhuli
Dudhouli, Sindhuli
Nepal

Addendum No: 1

Published On: 16-04-2020 12:00

Invitation No: FRM/Sindhuli/Works/NCB/06/076-77

Dated On: 20-03-2020 00:00

Following changes are made in the bid document

Chapter: General Information

Sl. No.	Relavant Clause No / Name	Existing Clause	Modified Clause
1	Clarification Submission Date	Not Provided in Bid Document	2020-04-16 12:00:00
2	Bid Submission DeadLine	2020-04-20 12:00:00	2020-04-30 12:00:00
3	Bid Opening Date	2020-04-20 13:00:00	2020-04-30 13:00:00
4	Authorised Representatives Address	Fikkal, Sindhuli Sindhuli Dudhouli	Fikkal, Sindhuli Sindhuli

Chapter: Bill of Quantities

1 Provisional Sum						
Procument Item Details						
SL. No	Item Description	Unit	Quantity	Unit Rate(in NPR)	Amount(in NPR)	
1	Insurance for the loss of damage to works, plant, materials, equipment, proporties and personal injury or death and 3rd parties as per contract data.	PS	1	50000	50000	
2 Construction work						
2.1 Works for complete or part construction and civil engineering work						
2.1.1 Building construction work						
Procument Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
1	Supplying and installation of UPVC Profile: Sliding window frame 50*80mm; sash 58*36mm, Sliding Door frame 52*88; sash 80*42, Casement window frame 60*60mm:sash 60*78mm, Casement Door frame 60*60; sash 60*104mm white colour with reinforcement, 5mm thick clear float glass, insect net, patented standard hardware like: rollers, gaskets, brush seal, moon locks, push locks, drinage cover, etc. (double Glazes glass)	m2	113.61			
2	3x20 mm iron Grill fixing works	m2	199.86			
3	Two coats Redoxid painting works	m2	469.93			
4	Two coats enamel painting works	m2	469.93			
5	Earthwork excavation in foundation of all types of soil including dewatering, shoring and strutting, preparing the bed for foundation mauually as per specification and as directed by A/E.	m3	31.05			
6	Dry stone soling, levelling work for foundation of rubble stone	m3	10.35			
7	PCC works in 1:3:6	m3	3.88			
8	Stone masonry works in 1:6 c/m with scaffolding	m3	20.7			
9	38 mm thick DPC in 1:2:4	m2	34.5			

Procument Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
10	12.5 mm thick cement plaster in 1:4 c/m	m2	201.25			
11	Chimany brick masonry works in 1:4 c/m	m3	51.36			
12	Two coats (weather Coat) painting works	m2	253.86			
13	Iron collapciable gate fixing works	m2	4.0			